


# LCLS Commissioning (Phase I)

C.Limborg-Deprey  
LCLS, SLAC



**LCLS**



Sept.24th 2007

# Outline

1. LCLS Project Overview
2. Injector Commissioning
  - Laser, Gun, Cathode, ...
  - Electron Beam Measurements
  - Some interesting beam physics ...
3. Comparison with simulations

PART 1:

LCLS Project

# Linac Coherent Light Source at SLAC

X-FEL based on last 1-km of existing linac

1.5-15 Å

Injector (35°)  
at 2-km point

Existing 1/3 Linac (1 km)  
(with modifications)

New  $e^-$  Transfer Line (340 m)

X-ray




LLNL

Transport  
Line (200 m)

Undulator (130 m)

Near Experiment Hall  
(underground)



Far Experiment  
Hall (underground)



# 3<sup>rd</sup> vs 4<sup>th</sup> Generation Light Sources



APS, USA      ESRF, Europe      Spring8, Japan      ...  
 ~ 15 years old  
 + newer SLS, SPEAR3, SOLEIL...

	3 <sup>rd</sup> GLS 	4 <sup>th</sup> GLS 
Peak Brilliance	$5 \cdot 10^{23}$	$10^{33}$
Coherent flux	$10^{10}$ /s /0.01%	$10^{13}$ / s/0.01%
Pulse Length	$\sigma \sim 10$ ps	$\sigma \sim 100$ fs (*)

(\*) or less with less flux

under construction



X-FEL, Germany      SCSS, Japan      LCLS, USA

# 4<sup>th</sup> Generation Light Sources

Peak Brilliance 10 orders of magnitude > that of 3<sup>rd</sup> GLS

- 2 from ↘ bunch length (10ps → 100fs)
- 2 from ↘ in horizontal emittance (3nm → 0.03nm)
- 1 from smaller divergence (SASE)
- 2 from longer undulator (~ 100m)
- 3 from FEL gain (SASE)

**But:** 3<sup>rd</sup> GLS

High repetition rate & High average brilliance


Stability decoupled from that of injector

# Nominal LCLS Parameters

Fundamental FEL Radiation Wavelength	<u>1.5</u>	<u>15</u>	Å
Electron Beam Energy	14.3	4.5	GeV
Normalized RMS Slice Emittance	1.2	1.2	mm-mrad
Peak Current	3.4	3.4	kA
Bunch/Pulse Length (FWHM)	230	230	fs
Relative Slice Energy Spread	<0.01	0.025	%
Saturation Length	87	25	m
FEL Fundamental Saturation Power	8	17	GW
FEL Photons per Pulse	1.1	29	$10^{12}$
Peak Brightness @ Undulator Exit	0.8	0.06	$10^{33}$ *
Transverse Coherence	Full	Full	
RMS Slice X-Ray Bandwidth	0.06	0.24	%
RMS Projected X-Ray Bandwidth	0.13	0.47	%

\* photons/sec/mm<sup>2</sup>/mrad<sup>2</sup>/ 0.1%-BW

# LCLS e-beam requirements



$\epsilon_N = 1.2 \text{ mm-rad}$

$$P = P_0$$

$\epsilon_N = 2.0 \text{ mm-rad}$


$$P = P_0/100$$

- Slice emittance  $\epsilon_{x/y,n} < 1.2 \text{ mm-mrad}$
- Slice energy spread  $\sigma_\delta < 10^{-4}$
- High Peak Current 3.4 kA ( $\sigma_\tau \sim 150 \text{ fs}$ )
- Stability  $dQ/Q < 2\% \text{ rms}$  ( $P \searrow 30\%$ )



# Nominal LCLS Parameters


Single bunch, 1-nC charge, 1.2- $\mu\text{m}$  slice emittance, 120-Hz repetition rate...




PART 2:

## LCLS Injector Commissioning

# Injector and 1<sup>st</sup> Bunch Compressor commissioning




# First Photo-Electrons, April 5, 2007



# Commissioning Milestones

- Spring 2006: Civil construction of buildings/shielding completed
- Summer 2006: Drive Laser Installed
- Fall 2006: Drive laser commissioned & Gun1 high power conditioning in Klystron Lab
- Spring 2007: Injector & BC1 beamline installed
- March 16, 2007: RF gun installed & RF processing started
- April 5, 2007: First Photo-electrons
- April 9, 2007: E-beam to 135 MeV
- April 16, 2007: E-beam to 250 MeV & compressed in BC1
- June 24, 2007: E-Beam to 15 GeV (200pC)
- July 24, 2007: E-Beam studies at 1 nC
- July 26, 2007: E-Beam at 1nC to 15 GeV
- August 8, 2007: Compressed 1 nC e-beam to 15 GeV
- August 2007: Injector Meets LCLS Requirements

# Thales Drive Laser System



Slide compliments Ph. Hering


# Drive Laser Performances

- Laser reliability is very good: Up-time > 90%
  - Excellent support from Thales & Femtolasers
- E ~ 400  $\mu$ J to cathode (250  $\mu$ J spec)
- Shaping needs work, but still producing good emittances
- Excellent energy stability (1.1%)
- Position stability on cathode, ~10-20  $\mu$ m


AVERAGE = 6.1289E+09  
RMS FIT ERROR = 6.5935E-01

## Laser stability vs. time


1.1% charge stability at 1nC, 2% is spec



9-AUG-07 22:33:36



**X-Correlator Measurement of Laser Pulse**






**Image of Laser Profile on Virtual Cathode Camera**

# RF Gun: 1.6 cell S-Band

Modified from BNL/UCLA/SLAC design

- Z-coupling:
  - reduces pulsed heating
  - increases vacuum pumping
- Racetrack to minimize quadrupole fields
- Deformation tuning to eliminate field emission from tuners
- Increased  $0-\pi$  mode separation to 15MHz
- Iris reshaped, reduces field 10% below cathode




<i>RF Parameters</i>	
$f_p$ (GHz)	<b>2.855987</b>
$Q_0$	<b>13960</b>
$\beta$	<b>2.1</b>
Mode Sep. $\Delta f$ (MHz)	<b>15</b>



# RF Gun: Processing and Operation


- Conditioning
    - 60Hz, 120 MV/m
    - 120Hz, 107 MV/m due to heating of probes
  - Operation
    - 30 Hz, 110MV/m, 1  $\mu$ s klystron pulse
    - $3 \cdot 10^8$  pulses
- (from April to Aug 07)



# Cathode Non-Uniformity


June 6, 2007

White light cathode image



June 2, 2007



Electron beam image of cathode @ ~9pC



- Emission is very non-uniform on the 10- $\mu\text{m}$  scale
- Perform ~weekly inspection of the cathode surface

courtesy D.Dowell

# Laser Cleaning: QE from $2 \cdot 10^{-6}$ to $4 \cdot 10^{-5}$



## Active cleaning:


RF on 1MV and at  $30^\circ$

Laser  $360 \mu\text{J}$  per  $\text{mm}^2$


Operation in Space Charge Limited regime

# Projected Emittances at 1nC


On-line analysis tools by H. Loos




Emittance Scan on OTRS:IN20:571 16-Aug-2007 17:40:26RMS cut area




Phase Space



Emittance Scan on OTRS:IN20:571 16-Aug-2007 17:40:26RMS cut area





Phase Space



Projected Emittance (rms) at 1nC  
(95% of the beam):  
 $\epsilon_x = 1.14 \text{ mm-mrad}$   
 $\epsilon_y = 1.06 \text{ mm-mrad}$

# Slice Emittances at 1nC


On-line analysis tools by H. Loos




## Slice Emittance, Current & Matching

Slices 3 to 7 (tail) are all below 1 mm-mrad  
 Head slices (8-10) are > 1 mm-mrad  
 Peak Current is 100 A

# Transverse Cavity (RF-Deflector) Measurements of Bunch Length



# Bunch Compression




$$V = V_0 \sin(\omega\tau)$$

RF Accelerating Voltage

$$\Delta z = R_{56} \Delta E/E$$







Path Length-Energy Dependent Beamline

# Linearization of Longitudinal Phase Space Measured Using RF Deflector & OTR Screen in Center of BC1






# Bunch Length Measurements at 135MeV & 15GeV




# Strong Optical Microbunching with BC1 Set to Maximum Compression

- Generation of COTR in the Visible indicates Microbunching
- COTR Interferes with OTR Profiles for Emittance Measurements.

Comparison of Bunch Length Monitor  
& OTR Signals




OTR Images Fluctuate from Shot-to-Shot  
& can produce “Ring-Like” Shapes!





# Coherent Optical Transition Radiation after DL1 Bend Even With No BC1 Compression

## Evidence of Optical Microbunching



Optical Signal from OTR screen with BC1 OFF depends on bend quad. Signal largest when quad at nominal (closing dispersion)



# BC1 Chicane Emittance Growth



Emittance Scan on WIRE:LI21:293 14-Aug-2007 22:23:28Gaussian



read BPMs while scanning BC1 mover

- Best  $\gamma\epsilon_x$  after BC1 with nom. (& more) compression is  $1.6 \mu\text{m}$  (& larger)
- Poor bend field quality (grad. + sext.) –  $\Delta E/E$  scan shows 1<sup>st</sup> & 2<sup>nd</sup>-order  $\eta$
- Screen image biased by COTR – wires vibrate – variable results (& in y)
- Bends will be upgraded in fall '07 + proper chirp set (now  $>2\%$  →  $1.6\%$ )

## PART 3:



### Simulations:

- effects of tails truncation in emittance computation
- comparison of emittance data along solenoid scan

# Initial Distribution


Spatial distribution based on laser profile (transverse and longitudinal)

Quiet start routine based on Halton sequences




# “Thermal” Emittance

## Based on Measurements



At 30 pC ,May 19<sup>th</sup>




30pC, July 3<sup>rd</sup> , after “cleaning”

Simulations used 0.6mm-mrad per mm





# Beamline Matched

Simulations try to represent at best experimental conditions






# Transverse Tails



IMPACT simulations (4 Million particles)

OTR2 image: resolution of 12  $\mu\text{m}$



# Emittance for various cut levels



Measurements give ~ 1-1.5 mm-mrad using 5 % area cut on beam size (highly reproducible result at 1nC)



Simulations predict similar result at 7.5% cut level

# Emission distribution used in simulations





Emission distribution needed for accurate distribution


# Longitudinal Profile



# Solenoid Scan





# Bunch length



**Laser Profile was 5ps FWHM**

# Emittance measurements

220 pC, projected emittance , in early commissioning



May 20<sup>th</sup> 2007 , from LCLS commissioning team

# Comparison of Required and Demonstrated Beam Properties

<b>Parameter</b>	<b>Sym</b>	<b>dsgn</b>	<b>meas.</b>	<b>unit</b>
<b>Final e<sup>-</sup> energy</b>	$\gamma mc^2$	15	15	GeV
<b>Bunch charge</b>	Q	1000	1000	pC
<b>Init. bunch length (fwhm)</b>	$\Delta t_0$	10	10	ps
<b>Fin. bunch length (fwhm)</b>	$\Delta t_f$	2.3	1.5	ps
<b>Initial peak current</b>	$I_{pk0}$	100	100	A
<b>Projected norm emittance</b>	$\gamma \epsilon_{x,y}$	1.2	1.1 to 1.3	$\mu\text{m}$
<b>Slice norm. emittance</b>	$\gamma \epsilon^s_{x,y}$	1.0	0.8, 0.9	$\mu\text{m}$
<b>Single bunch rep. rate</b>	f	120	10-30	Hz
<b>RF gun field at cathode</b>	$E_{cathode}$	120	115	MV/m
<b>Laser energy on cathode</b>	$U_l$	250	450	$\mu\text{J}$
<b>Laser wavelength</b>	$\lambda_l$	255	255	nm
<b>Laser diameter on cathode</b>	2R	1.5	1.3	mm
<b>Cathode material</b>	-	Cu	Cu	
<b>Cathode quantum eff.</b>	QE	6	3	$10^{-5}$
<b>Commissioning duration</b>	-	8	5	mo



**The LCLS Injector Commissioning Team:**

*Special Thanks  
to the LCLS Injector Team  
who allowed me to show their results.*

**R. Akre  
J. Castro  
Y. Ding  
D. Dowell  
P. Emma  
J. Frisch  
S. Gilevich  
G. Hays  
Ph. Hering  
Z. Huang  
R. Iverson  
C. Limborg-Deprey  
H. Loos  
A. Miahnahri  
J. Schmerge  
J. Turner  
J. Welch  
W. White  
J. Wu**

**And Our Visitors:**

**DESY**

**L. Froelich  
T. Limberg  
E. Prat  
M. Roehrs**

**Trieste**

**P. Craevich  
G. Penco  
M. Trovo**

**BESSY**

**T. Kamps**

- Merci pour votre attention