

# **SuperKEKB positron source status**

Takuya Kamitani (KEK)

# Positron source members

## ■ KEK

- ◆ Y. Enomoto, Yokoyama, Zang, Fukuda, Kamitani
- ◆ Tanaka, Ikeda, Kakihara, Arakida, Ohsawa, A. Enomoto
- ◆ Nakajima, Akemoto, S. Matsumoto, Higo
- ◆ Miura, Miyahara, Sugimoto, Seimiya, Iida, Ohnishi
- ◆ Okada, Takatomi, Someya, Kazama

## ■ Mitsubishi Electric System Service Co.

- ◆ Ushimoto, Suzuki, Kimura




## ■ Toyama Co.

- ◆ Iino, Morota, Sakai, Satoh


# SuperKEKB overview



Redesign the lattice to squeeze the emittance (replace short dipoles with longer ones, increase wiggler cycles)



New superconducting final focusing magnets near the IP



$e^+$  3.6A

$e^-$  2.6A

## SuperKEKB

- ◆ Nano-Beam scheme  
extremely small  $\beta_y^*$   
low emittance
- ◆ Beam current double

$$L = \frac{\gamma_{\pm}}{2er_e} \left( 1 + \frac{\sigma_y^*}{\sigma_x^*} \right) \left( \frac{I_{\pm} \xi_{\pm y}}{\beta_y^*} \right) \left( \frac{R_L}{R_y} \right)$$



40 times higher luminosity  
 $2.1 \times 10^{34} \rightarrow 8 \times 10^{35} \text{ cm}^{-2} \text{ s}^{-1}$

Improve monitors and control system


- Injector Linac upgrade
  - RF electron gun
  - improve  $e^+$  source

Injector Linac upgrade

New  $e^+$  Damping Ring



Replace beam pipes with TiN-coated antechamber-type ones




Wiggler sections upgrade



Reinforce RF systems for higher beam currents

# SuperKEKB Injector



## Upgrade items in positron source

Low emittance e+ : (2000 ->  $92_{[H]}/7_{[V]}$  mm)

- positron damping ring introduced

e+ intensity : (1 -> 4 nC/bunch)

- new positron focusing lens: flux concentrator (3.5 T) + bridge coils (1.0 T)
- large-aperture (2a=30mm) accelerating structure (LAS) in capture section
- positron focusing beam line layout reorganized with 100 new quad. magnets

# Double-deck pre-injectors

**Upper deck (former KEKB pre-injector, reconstructed !)**  
**thermionic gun + RF bunching section**

Gun 200 kV ( $\Rightarrow$  5 MV/m)

Sub Harmonic Buncher 1 (114 MHz)

Sub Harmonic Buncher 2 (571 MHz)

Prebuncher (2856 MHz)

Buncher (2856 MHz)

1300 ps


500 ps

330 ps

70 ps

10 ps

bunch  
length



**Lower deck**

**photo-cathode RF gun**

**+ magnetic bunching**


RF gun

Chicane

25 ps


10 ps

bunch  
length






# SuperKEKB positron source




# target offset & beam hole




- **injection e- beam** : on axis to preserve low emittance
- **primary e- beam** : 2.5 mm off axis to minimize e+ yield degradation  
(target offset 3.5 mm, FC offset 2.0mm)

# Positron Capture Section



operated at 10 MV/m  
with SLED detuned





- LAS with SLEDs for sufficient field gradient
- breakdown issue of LAS in solenoid field
- needs careful RF conditioning



# SuperKEKB e+ source (2015 August)

## ■ Fully equipped for commissioning

- ◆ FC assembly #1 (FC-base #3)
- ◆ 12-kA pulse modulator for FC
  - new coaxial cables
  - new triplate feeder line
  - snubber circuit
- ◆ Bridge Coils
- ◆ DC solenoids
- ◆ LAS accel. structures



# Topics after last POSIPOL

1. **Gas-bursting** of FC under bridge coil field in start-up for full current (12 kA) operation
2. FC-head **copper hardening** issue & FC teststand
3. Linac stand-alone **pre-commissioning** of e<sup>+</sup> source
4. e<sup>+</sup> status in **SuperKEKB Phase-1 commissioning**



# FC processing with Bridge Coil field

2015.09.24  
FC stable at  $I_{FC} = 11.5$  kA  
w/o BC field

2015.09.28  
Huge gas burst occurred  
at  $I_{FC} = 9.8$  kA @  $I_{BC} = 750$ A


2015.09.29  
Gas bursts occurred  
even w/o BC field

Irreversible damage in FC by breakdown !! → Operable current lowered -> 6 kA



# FC copper block work hardening

- In December, 2015, Y. Enomoto and T. Higo visited SLAC and discussed with the positron experts (A. Kulikov and E. Bong) on the FC gas bursting issue.
- They suggested that the **work hardening** of the OFC block of FC is **essential against the damage by breakdown**. (**We neglected this process!**)
- "Work hardening (strain hardening)" is a method of **strengthening of a metal by repeated plastic deformation**.
- When a **breakdown occurs** in FC, the spiral structure is **deformed but it springs back to the original shape** if it is work hardened.
- Unless work hardened, **deformation remains permanently** and makes very narrow gap in the slit.







# Hardening test of a sample block


## Hardening Procedure

1. Press FC-head till the gaps are contacted.
2. Insert spacers into the slit.
3. Remove the spacers.
4. Measure the gap size.
5. Repeat them from (1)



The natural gap size transfers to the spacer thickness (0.3 mm) by repeated hardening.

# work hardening ANSYS simulation





Pressing by 20 kgf force gives maximum stress 92 MPa in the FC-head. It exceeds the limit of plastic deformation for annealed copper (50 Mpa) and sufficient for work (strain) hardening.



# FC assembly #2 & test stand

- Operation test with BC field is essential. It is suggested FC vibration is larger under BC field.
- FC assembly #1 is radio-activated in the beam line.
- Construct **assembly #2** for operation with BC field at test stand.
- **Test-1**: operation with FC-head #4 (not work-hardened model) to see what happens in the same situation as the damaged FC-head #3.
  - non-hardened FC successfully achieved full-current (12 kA) operation with BC field (What's the difference to FC#3 ?)
- **Test-2**: operation with FC-head #5 (well work-hardened model) to check the operability at full current (12 kA) under the BC field.



# FC-head #5




Well work-hardened and installed in FC assembly #2. Test operation has recently started at test stand.




# Pre-commissioning performance (2015 Nov.)


- Beam tuning to optimize e+ yield performed in 2015 Oct ~ Dec.
- $I_{FC} = 6 \text{ kA}$  (design 12 kA) enhancement by FC  $\sim 1.8$
- $Q(e^-) = 6.3 \text{ nC @ target}$   
 $Q(e^+) = 1.9 \text{ nC at SY2}$   
 $Y(e^+) = 1.9/6.3 \Rightarrow 30 \%$  (design 50 %)



Y(e+) upon capture RF phase



Y(e+) upon FC pulse timing




Yield enhancement by FC (6 kA)  $\sim 1.8$

# SuperKEKB Phase-1 commissioning

- Phase-1 (2016 February -> June) operation condition
  - ◆ no beam collision
  - ◆ Superconducting Final Focusing system not installed
  - ◆ Belle-II detector not installed
  - ◆ e<sup>+</sup> damping ring not installed
- Goals in Phase-1 operation
  - ◆ start-up and tuning of machine components
  - ◆ beam scrubbing of vacuum components
  - ◆ low emittance tuning of storage rings (vertical emittance < 10 pm)
- Injection beam requirement
  - ◆ low intensity beam OK:  $Q(e^-) \sim 1 \text{ nC}$ ,  $Q(e^+) \sim 0.3 \text{ nC}$
  - ◆ large emittance beam accepted:  $(e^-) \sim 300 \text{ um}$ ,  $(e^+) \sim 1200 \text{ um}$

# SuperKEKB Phase-1 overview



Red: total beam current

Purple: vacuum pressure

Cyan: beam lifetime


HER: 870 mA,  $5.7 \times 10^{-8}$  Pa, ~200 min. (6/17)

LER: 1010mA,  $4.7 \times 10^{-7}$  Pa, ~60 min. (6/22)

achieved !

# SuperKEKB e<sup>+</sup> injection beam

## Typical e<sup>+</sup> injection beam at linac and BT-line




Beam collimators inserted to localize beam loss in low energy region.

Due to limited beam acceptance, inevitable beam loss occurs in linac & BT-line in direct injection w/o DR.



# SuperKEKB e<sup>+</sup> beam performance

## e<sup>+</sup> beam intensity history (2016 Jan ~ June)



# Summary

- 1) Breakdown in FC-head (#3) occurred under BC field gave a serious damage (September 2015) and operable current limited ~ 6 kA (half of the design value).
- 2) Importance of work-hardening process of FC-head was recognized. Test stand with new FC assembly #2 has been constructed to perform tests of non-hardened and well-hardened models with BC field. (June 2016 ~)
- 3) Positron yield  $Y(e^+) = 30\%$  ( $Q(e^+) = 1.9\text{nC}/Q(e^-) = 6.3\text{nC}$ ) achieved with 6 kA FC current at entrance of DR-LTR line. Stable  $e^+$  injection to LER has been achieved ( $Q(e^+)@BT\text{-end} \sim 0.3\text{nC} \times 2\text{-bunch}$ ) since February 2016. Beam loss in linac and BT line is due to operation w/o DR.
- 4) After finishing operation at test stand, FC assembly #2 will be installed in the beam line in March 2017. DR commissioning and LER injection in Phase-2 will be started in October 2017.