



ESRF-EBS : Mise en œuvre et mise en service, performance et redémarrage de l'exploitation utilisateurs

Jean-Luc Revol

On behalf of the ESRF Accelerator and Source Division



- The ESRF-EBS project
- Implementation and start-up
- Commissioning and restart of user operation
- COVID-19 pandemic: impact and lessons learnt



ESRF FACTS AND FIGURES


Light source in operation since 1994

Located in Grenoble, France

22 partner nations


Annual budget: 100 million euros

Staff: 650




The ESRF Extremely Brilliant Source upgrade :


- Decrease the horizontal emittance
 - Increase the source brilliance
 - Increase the source coherence



THE ESRF-EBS UPGRADE




	Units	ESRF	ESRF-EBS
Energy	GeV	6	6
Circumference	m	844.4	844
Lattice		DBA	HMBA
Current	mA	200	200
Lifetime	h	50	25
Emittance H	pm.rad	4000	133
Emittance V	pm.rad	4	10*



31 magnets per cell instead of 17

ESRF-EBS PROJECT IMPLEMENTATION



Old ESRF-Storage Ring




- October 2017** Start of girder assembly
10 December 2018 End USM, start shutdown
Dismantling
Installation
8 November 2019 Tunnel closed
Tests & Injector restart
28 November 2019 Accelerator commissioning
2 March 2020 Beamline commissioning
25 August 2020 Start User Mode Operation

ESRF-EBS




ESRF-EBS: INSTALLATION IN THE TUNNEL




December 2018

November 2019


ESRF-EBS: COMMISSIONING




28th November
First turns



6th December
Beam stored




15th December
Accumulation



30th January
First Beam on
26 Beamlines




28th February
200 mA achieved




ESRF-EBS: EQUIPMENT COMMISSIONING


- **Control software, optics tools, commissioning scripts validated prior and during shutdown on the Storage Ring simulator**
- **Low and high level control for all equipment (including vacuum):**
 - ➔ Started as soon as the cabling is done
- **Power test of the magnets** from August to November with tunnel not accessible
- **During last weeks of the shutdown with tunnel close** (14/10 to 28/11):
 - ➔ Final alignment & survey
 - ➔ Validation of the personal safety system
 - ➔ Global power test of the magnets
 - ➔ Interlocks
 - ➔ Injection/extraction elements
 - ➔ Radio-frequency power commissioning
 - ➔ **Injector commissioning**



ESRF-EBS: BEAM COMMISSIONING OBSTACLES



ESRF-EBS: BEAM COMMISSIONING VACUUM ISSUE




A Few ID NEG coated ID chambers with poor vacuum

ID12 was contaminated → poor vacuum → replaced

Replacement


Reactivation



Detected, resolved by:


- Very useful beam loss diagnostics for detection
- Intervention to exchange the chamber
- Lifetime increase by a factor 3

ESRF-EBS: BEAM COMMISSIONING OPTICS TUNING




Optics tuning:

- Optics correction** (magnet modeling)
Add magnetic cross talk between adjacent magnets
Correct wrong calibration factor
Excellent alignment of components(<50 μm in both plane)
- Orbit steering**
Beam base alignment (100 μm rms both plane)
Eigen vector optimization (from 64 to 162)
Eigen mode analysis (correction of DQs missing angle)
- Lattice re-correction after BM sources (SB and 2PW) installation
- Coupling correction** ($\epsilon_v < 1\text{pm}.\text{rad}$)
- Dynamic aperture and injection efficiency studies
(Still lower than model)
- Automatic lifetime/losses optimizer
(sextupoles, octupoles, skew scanning)



ESRF-EBS: COMMISSIONING FROM 28/11 TO 01/04





LESSONS LEARNED FROM THE INSTALLATION AND THE COMMISSIONING

- ✓ Large benefit from phase 1 upgrade for the infrastructure and accelerator components
- ✓ Capitalize on the expertise for installation and start-up gained on the existing facility prior upgrade (*staff, procedures, control...*)
- ✓ Pre-assembly and anticipated tasks executed prior the shutdown
- ✓ Design, procurement and installation procedures validated on the mockup
- ✓ Activities concentrated on the storage ring during installation, limited activity for beamlines & infrastructure
- ✓ Validation of control and tools on a simulator
- ✓ Equipment test started as soon as possible, including control system
- ✓ All systems (RF, diagnostics, power,...) operational and reliable from start of commissioning
- ✓ Efficient beam position monitor and beam loss detectors available from the start of commissioning



ESRF-EBS IMPACT OF COVID-19 PANDEMIC



→ 28 Feb. 2020 plan: Machine ready for beamlines

→ Achieved

→ 03 March 2020 plan: Start of beamline commissioning → Achieved

But: 17-03/20 to 11/05/20: **First lockdown in France** (declared on 14/03/20)

→ ESRF Closure → Stop operation

→ 25 August 2020 plan: Start of user operation


→ Achieved

But: 30/10/20 to 15/12/20: **Second lockdown**

03/04/21 to 03/05/21: **Third lockdown**

→ Adaptation of the operation planning for users


COVID-19 impacted the schedule as of 14 March 2020 (only),
affecting mostly the beamline and user programme



ESRF AT THE TIME OF THE COVID-19 PANDEMIC

- Ensuring safe working conditions on site , strictly following French regulations
- Objective: Restarting user service mode (USM) on 25 August 2020 with a maximum number of beamlines open

→ ESRF KEPT FULLY OPERATIONAL FROM 25-08-2020 TO DATE!



IMPACT OF COVID-19 FOR THE OPERATION

Jan 2020	Feb 2020	Mar 2020	Apr 2020	May 2020	Jun 2020	Jul 2020	Aug 2020	Sep 2020	Oct 2020	Nov 2020	Dec 2020
Wed 01 s s s	Sat 01 M C M	Sun 01 M M M	Wed 01 s s s	Fri 01 B B B	Mon 01 M M M	Mon 01 B B B	Wed 01 . . .	Sat 01 s s s	Thu 01 . . .	Tue 01 B B B	
Thu 02 s s s	Sat 02 B B B	Sun 02 M M C	Mon 02 B B B	Thu 02 s s s	Sat 02 B B B	Tue 02 B B B	Wed 02 . . .	Sat 01 s s s	Mon 02 . . .	Wed 02 . . .	
Fri 03 s s s	Sun 03 M C M	Mon 03 M C M	Tue 03 B B B	Fri 03 s s s	Sun 03 s s s	Mon 03 B B B	Wed 03 . . .	Tue 03 B B B	Mon 03 s s s	Thu 03 . . .	
Sat 04 s s s	Tue 04 B B B	Sat 04 s s s	Mon 04 s s s	Thu 04 B B B	Sat 04 B B B	Tue 04 B B B	Wed 04 . . .	Sat 04 B B B	Fri 04 . . .	Sun 04 . . .	
Sun 05 s s s	Mon 05 M C M	Mon 05 M C M	Tue 05 B B B	Sun 05 s s s	Mon 05 B B B	Tue 05 B B B	Wed 05 . . .	Sun 05 B B B	Mon 06 . . .	Mon 06 B B B	
Mon 06 s s s	Tue 06 B B B	Mon 06 M C M	Wed 06 B B B	Sun 06 s s s	Mon 06 B B B	Tue 06 B B B	Wed 06 . . .	Sun 06 B B B	Mon 07 M M M	Mon 07 M M M	
Tue 07 s s s	Wed 07 B B B	Tue 07 M C M	Thu 07 B B B	Sat 07 s s s	Mon 07 B B B	Tue 07 B B B	Wed 07 . . .	Sat 07 B B B	Mon 07 B B B	Mon 07 M M M	
Wed 08 s s s	Sat 08 B B B	Sun 08 M C M	Mon 08 B B B	Thu 08 s s s	Wed 08 B B B	Fri 08 B B B	Thu 08 . . .	Sat 08 B B B	Mon 09 M M C	Mon 09 M M C	
Thu 09 s s s	Sun 09 M C M	Mon 09 M M C	Tue 09 B B B	Sat 09 s s s	Mon 09 B B B	Tue 09 B B B	Wed 09 . . .	Sat 09 B B B	Mon 10 B B M	Mon 10 B B M	
Fri 10 s s s	Sun 10 M C M	Mon 10 M C M	Tue 10 B B B	Fri 10 s s s	Sat 10 B B B	Tue 10 B B B	Wed 10 . . .	Sat 10 B B B	Mon 11 B B M	Mon 11 B B M	
Sat 11 s s s	Tue 11 B B M	Sat 11 s s s	Wed 11 B B B	Sat 11 s s s	Tue 11 B B B	Sat 11 s s s	Tue 11 . . .	Sat 11 s s s	Tue 11 B B M	Tue 11 B B M	
Sun 12 s s s	Wed 12 B B M	Sun 12 s s s	Mon 12 B B B	Sun 12 s s s	Wed 12 B B B	Mon 12 B B B	Wed 12 . . .	Sun 12 s s s	Mon 13 B B M	Mon 13 B B M	
Mon 13 s s s	Tue 13 B B M	Mon 13 s s s	Wed 13 B B B	Sun 13 s s s	Mon 13 B B B	Tue 13 B B B	Wed 13 . . .	Sun 13 s s s	Tue 14 B B M	Tue 14 B B M	
Tue 14 s s s	Wed 14 B B M	Tue 14 s s s	Thu 14 B B M	Sun 14 s s s	Mon 14 B B M	Tue 14 M M M	Wed 14 . . .	Sun 14 s s s	Mon 15 M M M	Mon 15 M M M	
Wed 15 s s s	Sat 15 s s s	Sun 15 s s s	Mon 15 s s s	Wed 15 B B M	Tue 15 B B M	Thu 15 M M M	Fri 15 . . .	Sat 15 s s s	Sun 16 M C M	Sun 16 M C M	
Thu 16 s s s	Sun 16 M C M	Sun 16 s s s	Mon 16 s s s	Tue 16 B B M	Sat 16 s s s	Mon 16 B B M	Wed 16 . . .	Sun 16 M C M	Mon 17 B B M	Mon 17 B B M	
Fri 17 M C M	Mon 17 s s s	Tue 17 s s s	Wed 17 B B M	Sat 17 s s s	Fri 17 B B M	Mon 17 s s s	Thu 17 . . .	Sat 17 s s s	Tue 18 B B M	Tue 18 B B M	
Sat 18 M M C	Tue 18 s s s	Wed 18 s s s	Thu 18 B B M	Sat 18 s s s	Sun 18 B B M	Tue 18 B B M	Wed 18 . . .	Sun 18 s s s	Mon 19 B B M	Mon 19 B B M	
Sun 19 M M C	Wed 19 s s s	Thu 19 s s s	Mon 19 B B M	Sun 19 s s s	Mon 19 B B M	Wed 19 s s s	Thu 19 . . .	Sun 19 s s s	Tue 20 B B M	Tue 20 B B M	
Mon 20 M M C	Thu 20 s s s	Mon 20 s s s	Tue 20 B B M	Sun 20 s s s	Mon 20 B B M	Thu 20 B B M	Mon 20 . . .	Sun 20 s s s	Tue 21 B B M	Tue 21 B B M	
Tue 21 M M C	Fri 21 B B M	Tue 21 s s s	Wed 21 B B M	Sun 21 s s s	Tue 21 B B M	Fri 21 M M M	Mon 21 . . .	Tue 21 s s s	Wed 22 B B M	Wed 22 B B M	
Wed 22 B B M	Sat 22 B B M	Sun 22 B B M	Mon 22 B B M	Tue 22 B B M	Sat 22 B B M	Mon 22 B B M	Wed 22 . . .	Sun 22 B B M	Mon 23 M M C	Mon 23 M M C	
Thu 23 M M C	Sun 23 B B M	Sun 23 M M C	Mon 23 M M C	Tue 23 B B M	Sat 23 B B M	Mon 23 B B M	Wed 23 . . .	Sun 23 M M C	Tue 24 B B M	Tue 24 B B M	
Fri 24 M M C	Mon 24 B B M	Mon 24 M M C	Tue 24 B B M	Sat 24 s s s	Fri 24 B B M	Mon 24 M M C	Wed 24 . . .	Mon 24 M M C	Tue 25 B B M	Tue 25 B B M	
Sat 25 M M C	Tue 25 B B M	Tue 25 M M C	Wed 25 B B M	Sat 25 s s s	Sat 25 B B M	Tue 25 B B M	Thu 25 . . .	Sat 25 s s s	Mon 26 B B M	Mon 26 B B M	
Sun 26 M M C	Wed 26 B B M	Thu 26 B B M	Sun 26 B B M	Tue 26 B B M	Mon 26 B B M	Wed 26 B B M	Thu 26 . . .	Sun 26 s s s	Tue 27 B B M	Tue 27 B B M	
Mon 27 M M C	Thu 27 B B M	Mon 27 s s s	Wed 27 B B M	Sat 27 B B M	Mon 27 s s s	Thu 27 B B M	Mon 27 . . .	Sat 27 s s s	Tue 28 B B M	Tue 28 B B M	
Tue 28 M M C	Fri 28 B B M	Sat 28 s s s	Thu 28 B B M	Sun 28 B B M	Tue 28 B B M	Fri 28 B B M	Mon 28 . . .	Sat 28 s s s	Mon 29 M M C	Mon 29 M M C	
Wed 29 B B M	Sat 29 B B M	Sat 29 M M C	Sun 29 B B M	Mon 29 M M C	Wed 29 s s s	Mon 29 M M C	Thu 29 . . .	Sun 29 s s s	Mon 30 M M C	Mon 30 M M C	
Thu 30 M M C	Mon 30 s s s	Thu 30 M M C	Mon 30 B B B	Tue 30 s s s	Mon 30 B B B	Tue 30 s s s	Wed 30 . . .	Mon 30 M M C	Mon 30 M M C	Mon 30 M M C	
Fri 31 M M C	Tue 31 s s s	Sun 31 B B B	Sun 31 s s s	Mon 31 s s s	Sun 31 B B B	Sun 31 s s s	Mon 31 . . .	Sun 31 s s s	Sun 31 B B B	Sun 31 s s s	

COVID-19 first lockdown

Second lockdown

Machine Commissioning

Beamline Commissioning

janv 2021	févr 2021	mars 2021	avr 2021	mai 2021	juin 2021	juill 2021	août 2021	sept 2021	oct 2021	nov 2021	déc 2021
ven 01 s s s	Sat 01 . . .	Sun 01 M M M	Mon 01 . . .	Thu 01 . . .	Sat 01 . . .	Mon 01 . . .	Thu 01 . . .	Sun 01 s s s	Mon 01 . . .	Mer 01 . . .	Mer 01 . . .
Thu 02 s s s	Sat 02 B B B	Sun 02 B B B	Mon 02 B B B	Thu 02 B B B	Sat 02 B B B	Mon 02 B B B	Thu 02 . . .	Sun 02 B B B	Mon 02 M M M	Sam 02 . . .	Sam 02 . . .
Fri 03 s s s	Sun 03 s s s	Mon 03 s s s	Tue 03 B B B	Fri 03 s s s	Sun 03 s s s	Mon 03 s s s	Wed 03 . . .	Sat 03 B B B	Mon 03 M M C	Mer 03 . . .	Mer 03 . . .
Sat 04 s s s	Tue 04 B B B	Sat 04 s s s	Mon 04 s s s	Thu 04 B B B	Sat 04 B B B	Tue 04 B B B	Wed 04 . . .	Sat 04 B B B	Fri 04 . . .	Jeu 04 . . .	Jeu 04 . . .
Sun 05 s s s	Mon 05 B B B	Sun 05 M C M	Tue 05 B B B	Sat 05 s s s	Mon 05 B B B	Tue 05 B B B	Wed 05 . . .	Sun 05 B B B	Mon 06 M M C	Mer 05 . . .	Mer 05 . . .
Mon 06 s s s	Tue 06 B B B	Mon 06 M C M	Wed 06 B B B	Sun 06 s s s	Mon 06 B B B	Tue 06 B B B	Wed 06 . . .	Sun 06 B B B	Mon 07 M M M	Mer 06 . . .	Mer 06 . . .
Tue 07 s s s	Wed 07 B B B	Tue 07 M C M	Thu 07 B B B	Sat 07 s s s	Mon 07 B B B	Tue 07 B B B	Wed 07 . . .	Sat 07 B B B	Mon 07 M M M	Mer 07 . . .	Mer 07 . . .
Wed 08 s s s	Sat 08 B B B	Sun 08 M C M	Mon 08 B B B	Thu 08 s s s	Wed 08 B B B	Fri 08 B B B	Thu 08 . . .	Sat 08 B B B	Mon 09 M M C	Sam 09 . . .	Sam 09 . . .
Thu 09 s s s	Sun 09 M C M	Mon 09 M M C	Tue 09 B B B	Sat 09 s s s	Mon 09 B B B	Tue 09 B B B	Wed 09 . . .	Sat 09 B B B	Mon 10 B B M	Sam 10 . . .	Sam 10 . . .
Fri 10 s s s	Sun 10 M C M	Mon 10 M C M	Tue 10 B B B	Fri 10 s s s	Sat 10 B B B	Tue 10 B B B	Wed 10 . . .	Sat 10 B B B	Mon 11 B B M	Jeu 11 . . .	Jeu 11 . . .
Sat 11 s s s	Tue 11 B B M	Sat 11 s s s	Wed 11 B B B	Sat 11 s s s	Tue 11 B B B	Sat 11 s s s	Tue 11 . . .	Sat 11 s s s	Tue 11 B B M	Sam 12 . . .	Sam 12 . . .
Sun 12 s s s	Mon 12 B B M	Sun 12 s s s	Tue 12 B B B	Sun 12 s s s	Mon 12 B B B	Tue 12 B B B	Wed 12 . . .	Sun 12 s s s	Mon 13 B B M	Sam 13 . . .	Sam 13 . . .
Mon 13 s s s	Tue 13 B B M	Mon 13 s s s	Wed 13 B B B	Sun 13 s s s	Mon 13 B B B	Tue 13 B B B	Wed 13 . . .	Sun 13 s s s	Tue 14 B B M	Mer 14 . . .	Mer 14 . . .
Tue 14 s s s	Wed 14 B B M	Tue 14 s s s	Thu 14 B B M	Sun 14 s s s	Mon 14 B B M	Tue 14 M M M	Wed 14 . . .	Sun 14 s s s	Mon 15 M M M	Sam 15 . . .	Sam 15 . . .
Wed 15 s s s	Sat 15 s s s	Sun 15 s s s	Mon 15 s s s	Wed 15 B B M	Tue 15 B B M	Thu 15 M M M	Fri 15 . . .	Sat 15 s s s	Sun 16 M C M	Sun 16 M C M	Sun 16 M C M
Thu 16 s s s	Sun 16 M C M	Sun 16 s s s	Mon 16 s s s	Tue 16 B B M	Sat 16 s s s	Mon 16 B B M	Wed 16 . . .	Sun 16 M C M	Mon 17 B B M	Mer 17 . . .	Mer 17 . . .
Fri 17 M C M	Mon 17 s s s	Tue 17 s s s	Wed 17 B B M	Sat 17 s s s	Fri 17 B B M	Mon 17 s s s	Thu 17 . . .	Sat 17 s s s	Tue 18 B B M	Sam 18 . . .	Sam 18 . . .
Sat 18 M M C	Tue 18 s s s	Wed 18 s s s	Thu 18 B B M	Sat 18 s s s	Sun 18 B B M	Tue 18 B B M	Wed 18 . . .	Sun 18 s s s	Mon 19 B B M	Sam 19 . . .	Sam 19 . . .
Sun 19 M M C	Wed 19 s s s	Thu 19 s s s	Mon 19 B B M	Sun 19 s s s	Mon 19 B B M	Wed 19 s s s	Thu 19 . . .	Sun 19 s s s	Tue 20 B B M	Sam 20 . . .	Sam 20 . . .
Mon 20 M M C	Thu 20 s s s	Mon 20 s s s	Tue 20 B B M	Sun 20 s s s	Mon 20 B B M	Thu 20 B B M	Mon 20 . . .	Sun 20 s s s	Tue 21 B B M	Sam 21 . . .	Sam 21 . . .
Tue 21 M M C	Fri 21 B B M	Tue 21 s s s	Wed 21 B B M	Sun 21 s s s	Tue 21 B B M	Fri 21 M M M	Mon 21 . . .	Tue 21 s s s	Wed 22 B B M	Mer 22 . . .	Mer 22 . . .
Wed 22 B B M	Sat 22 B B M	Sun 22 B B M	Mon 22 B B M	Tue 22 B B M	Sat 22 B B M	Mon 22 B B M	Wed 22 . . .	Sun 22 B B M	Tue 23 M M C	Sam 23 . . .	Sam 23 . . .
Thu 23 M M C	Sun 23 B B M	Sun 23 M M C	Mon 23 M M C	Tue 23 B B M	Sat 23 B B M	Mon 23 B B M	Wed 23 . . .	Sun 23 M M C	Thu 24 B B M	Sam 24 . . .	Sam 24 . . .
Fri 24 M M C	Mon 24 B B M	Mon 24 M M C	Tue 24 B B M	Sat 24 s s s	Fri 24 B B M	Mon 24 M M C	Wed 24 . . .	Mon 24 M M C	Thu 25 B B M	Sam 25 . . .	Sam 25 . . .
Sat 25 M M C	Tue 25 B B M	Tue 25 M M C	Wed 25 B B M	Sat 25 s s s	Sat 25 B B M	Tue 25 B B M	Thu 25 . . .	Sat 25 s s s	Mon 26 B B M	Sam 26 . . .	Sam 26 . . .
Sun 26 M M C	Wed 26 B B M	Thu 26 B B M	Sun 26 B B M	Tue 26 B B M	Mon 26 B B M	Wed 26 B B M	Thu 26 . . .	Sun 26 B B M	Tue 27 B B M	Sam 27 . . .	Sam 27 . . .
Mon 27 M M C	Thu 27 B B M	Mon 27 s s s	Wed 27 B B M	Sat 27 s s s	Mon 27 B B M	Thu 27 B B M	Mon 27 . . .	Sat 27 s s s	Tue 28 B B M	Sam 28 . . .	Sam 28 . . .
Tue 28 M M C	Fri 28 B B M	Sat 28 s s s	Thu 28 B B M	Sun 28 B B M	Tue 28 B B M	Fri 28 B B M	Mon 28 . . .	Sat 28 s s s	Mon 29 M M C	Sam 29 . . .	Sam 29 . . .
Wed 29 B B M	Sat 29 B B M	Sat 29 M M C	Sun 29 B B M	Mon 29 M M C	Wed 29 s s s	Mon 29 M M C	Thu 29 . . .	Sun 29 s s s	Mon 30 M M C	Sam 30 . . .	Sam 30 . . .
Thu 30 M M C	Mon 30 s s s	Thu 30 M M C	Mon 30 B B B	Tue 30 s s s	Mon 30 B B B	Tue 30 s s s	Wed 30 . . .	Mon 30 M M C	Mon 30 M M C	Sam 31 M M M	Sam 31 M M M
Fri 31 M M C	Tue 31 s s s	Sun 31 B B B	Sun 31 s s s	Mon 31 s s s	Sun 31 B B B	Sun 31 s s s	Mon 31 . . .	Sun 31 s s s	Sun 31 B B B	Sun 31 s s s	Sun 31 M M M

Second lockdown

Third lockdown

Machine Commissioning

Beamline Commissioning

August 2020

USM

From the start of the second lockdown to summer 2021,
number of user shifts [blue] reduced (3&4 days /week).

Limited access to the site:

- Opportunity to improve tools for remote control
- Dedicated chat channels, Confluence, JIRA and Jlogbook have been actively used
- Development shifts /interventions were often performed via video-conferencing
→ Very efficient for short and fast support, including activities with beamlines

Video-conferencing and remote control are new operation tools for the future



RETURN TO OPERATION: ONGOING REMOTE ACCESS EXPERIMENTS



Gary Harlow
@garyharlow

I've taken over the dining table for our (now) remote beamtime at @esrf_id31 @SoM_esrf investigating ORR on stepped surfaces with high energy surface x-ray diffraction.

[Traduire le Tweet](#)



IMPLEMENTING REMOTE ACCESS SOLUTIONS TO KEEP SCIENCE AT THE FOREFRONT

- New protocols for user programme operation, so that a majority of experiments can be conducted or followed up remotely
- Implementation new solutions that allows users to interact remotely with beamline control software and tools
- Implementation of large-scale sample mail-in solutions for user experiments
- Remote data analysis with improved data transfer

USER STATISTICS AND ACTIVITIES – 25 AUGUST 2020 TO 31 JULY 2021



FIRST USM YEAR WITH THE NEW EBS STORAGE RING A MILESTONE FOR THE X-RAY COMMUNITY

43/44

13 175

1 872

1 262

43 out of 44
beamlines hosted
user experiments




13 175 shifts delivered
(105 400 hours)

1 872 user
experiments

1262 fully remote (68%),
192 only one user (10%),
and 418 with users (22%)



BEAM DELIVERY FROM 25/08/2020 TO 29/09/2021




	7/8 + 1	Uniform	32*12	28*12+1	62 bunch	16 bunch	4 bunch
I_{max} (mA)	196+4 * (192+8)	200	150 * (200)	125+3* (200)	65*	35* (90)	20* (40)
Lifetime (hours)	> 22	> 25	> 22	> 23	~ 14	~ 8	~ 5
ε_v (pm) *	10	10	20	20	20	20	20

* Intensity limitation for timing modes due to mechanical weakness of the kicker ceramic chambers


* Vertical emittance artificially increased from 1 to 10 pm rad for an operational lifetime

* All timing modes delivered with a purity of 10^{-9} with cleaning process in the booster


BEAM DELIVERY SINCE THE START OF USM



Some disturbed weeks !!




But also quiet time !




- Overall reliability comparable to that of the old source
- Magnet power supply system was the most complex hardware to develop and commission
 - ✓ *Hot swap system under commissioning*
- Human mistakes due to development (*mostly at the beginning*)
- Infrastructure (*mains, cooling, doors*)
- Operation disturbed by a few long failures from sub-systems not linked to EBS design
 - ✓ *aluminum NEG coated ID vacuum chambers*
 - ✓ *RF master source*
 - ✓ *20 KV high voltage cable defect*
- RF highly reliable


	2017	2018	2020	2021
	EBS	EBS		
Availability (%)	98.3	98.5	96.1	98
Mean time between failures (hrs)	64.3	104.3	46.0	73.4
Mean duration of a failure (hrs)	1.11	1.60	1.80	1.46



OVERVIEW: BEAM CURRENT & LIFETIME



VERTICAL AND HORIZONTAL EMITTANCES FROM 25/08/2020 TO 29/09/2021



25/08/2020

Horizontal emittance diagnostics modified and calibrated during run 2020-06 and run 2021-1

➔ Typical today: $130 \pm 20 \text{ pm.rad}$

Vertical emittance artificially blown up using white noise excitation up
from 1 pm.rad to 10 or 20 pm.rad to get an operational lifetime

➔ Typical today: $10 \text{ pm} \pm 1 \text{ pm.rad}$

ESRF-EBS: PARAMETER ACHIEVED

	Design	Realized today
Total current	200,90,40 mA	200, 35, 20 mA
MTBF	> 30 h	> 70 h
Up-Time	98%	98 %
Injection Efficiency	> 90 %	> 80 %
Lifetime	> 20 h	> 25 h
ε_H	< 140 pm rad	< 130±20 pm rad
ε_V	10 pm rad	10 pm rad
Stability	< 0.05 σ	< 0.01 σ

Results:

- Despite the impact of the Covid-19 pandemic, users recovered the beam on the scheduled day and with an adapted operation planning
 - Main performances achieved (beam current, beam modes, lifetime, emittances, stability)
 - Excellent reliability of the hardware
 - Delay in the beamline commissioning and upgrade programme
 - Additional operating and support tools and methods have emerged
- Beamlines are now progressing and upgrading to take full benefit of the source
- Users are starting to come back

Objectives for the machine:

- Fine tuning of beam parameters
- Implementation of the hot-swap system for the power supplies
- Reduce injection perturbation and go back to injection from every 1hour to every 20 mn
- Nominal beam current in time-structured modes

MANY THANKS FOR YOUR ATTENTION

